

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Barton

County. Sec. 16 Twp. 20 Rge. 11 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner Tomlinson Kathol

Lease Name Scheufler Well No. 5

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 1/3/67 19

Plugging completed 1/9/67 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Truan

Producing formation Depth to top Bottom Total Depth of Well 330 1/2 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	FROM	TO	SIZE	PUT IN	PULLED OUT
			8 5/8	324	none
			4 1/2	3293	1596
RECEIVED FROM JAN 24 1967 CONSERVATION DIVISION WICHITA, KANSAS					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Raised mast, checked hole to 3247', sanded to 3220' and ran 3 sacks of cement. Cleaned cellar. Rigged up on 5 1/2" casing, parted pipe, pulled 6 joints, went and got overshot, ran it down the hole, got hole of 4 1/2". Shot pipe at 2581', worked pipe. Shot pipe at 2208', 2000', 1910', 1806', no change in tension. Lost 1200' wire line in hole. Fished wire line out of hole, shot pipe at 1702', 1594', worked pipe loose. Pulled 40 joints 4 1/2" casing. Finished pulling 4 1/2" casing, 64 joints total. Cleared floor, loaded rack, bailed hole to 300', 10' rock bridge and ran 25 sacks cement. Mudded hole to 40', 10' rock bridge and ran 10 sacks cement. Tallied pipe. Racked unit.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 11 day of Jan, 1967

My commission expires Oct 22, 1970 Notary Public.

WELL LOG

SCHUEFLER #5

The Henderson Oil Company et al - owners - Schuefler #5  
SE Cor.  
Section 16-20-11W  
Barton County, Kansas

Elevation 1771 NN

Logs at Rotary Boring

Topoka 2641  
Hickory 2908  
Brown Lims 3034  
Lansing 3092  
Arkusks 3295

Pipe Records

8 5/8" set at 324'

4 1/2" set at 3296'

Figures indicate bottom of formation

0 - 128 Sand and Gravel  
165 Shale  
200 Gravel and sand  
310 Red bed and shale  
540 Anhydrite  
1015 Shale and shells  
1200 Salt and shale  
1425 Shale and shells  
2120 Lims  
2565 Shale and lins  
2750 Lims and shale  
2925 Lims  
3040 Shale and lins  
3296 Lims  
3296 TB NN

3293  
1771  
-1522

CABLE TOOL WORK

Clean out and drill cement  
3296-3305' Lims

3032  
1771  
1281

STATE OF KANSAS }  
COUNTY OF SEDGWICK } SS

I, J. A. Henderson, Secretary of The Henderson Oil Company, part owner of the above described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements, and matters herein contained pertaining to the log of the above described well, and that the same are true and correct.

Sworn and subscribed to before me this \_\_\_\_\_

My commission expires April 25, 1914.

15.009.04852.0000

## WAYNE E. WALCHER

Consultant Geologist

CENTRAL BUILDING  
WICHITA, KANSAS

## WELL REPORT

November 22, 1950 #19The Henderson Oil Company No. 5 Scheufler  
SE SE SE 16-20-11W, Barton County, KansasZero - - - - Drive Bushing, 2' above derrick floor  
Elev. 1771 - " "

Soft	2625-41	Sand, gray, fine-grained, micaceous, no stain.
Topeka	2641 (-870)	
Soft	2738-40	Lime, buff, pin-hole porosity, no stain.
Soft	2823-38	Lime, cream, finely oolitic porosity, no stain.
Soft	2861-73	Lime, cream-white, compact and chalky, poor porosity, no stain.
Heebner	2908 (-1137)	
Toronto	2926	
Base Oread	2940	
Brown Lime	3034 (-2263)	
Lansing	3052 (-1282)	
Stain	3061-65	Lime, white-tan, dense with rare sucrose areas, fair spotted stain. No odor.
Stain	3075-78	Lime, semi-oolitic, tight, spotted dark stain. Few pieces poorly developed inter-oolite porosity, faint odor.
D. S. T.	3062-85	Open 30 minutes, recovered 15' mud, few spots heavy oil. No BHP.
Stain	3135-40	Lime, coarsely oolitic porosity, in part sucrose, light spotted stain, breaks free oil, faint odor.
Stain	3182-90	Lime, poorly developed oolitic porosity, trace free oil, fair odor and rainbow.
D. S. T.	3182-3301	Open 30 minutes, recovered 10' mud, very slightly oil out. No BHP.
Stain	3281-85	Lime, fine, dense, with trace sugary areas of poor porosity and dark stain, odor, no free oil.
No Conglomerate Arbuckle	3293 (-1522) 3293-96	Dolomite, light gray, medium to coarse cryst. predominately tight but few pieces show fair vugular porosity, light stain, trace free oil and good odor.
Rotary T. D.	3296	4" casing @ 3293½.



15.009.04852.0000

## WAYNE E. WALCHER

*Consultant Geologist*CENTRAL BUILDING  
WICHITA, KANSAS

On top of the Arbuckle S -1522 this test is 9 feet higher than the east offset and 12' higher than the north offset.

Before final abandonment, the shows of oil listed in the Lansing-Kansas City should be tested. They all seem to lack permeability, or at least three zones in this well and one in the east offset have failed to give up fluid on B.S.F. However, acid treatment might prove commercial.



15.009.04852.0000

WAYNE E. WALCHER

Consultant Geologist

CENTRAL BUILDING

WICHITA, KANSAS

The Henderson Oil Company No. 5 Scheufler  
SE SE SE 16-20-11W, Barton County, Kansas

TIME LOG

From	To	Minutes	Remarks
2600	2610	4-6-4-2-1-2-2-2-2-2	
	2620	2-2-2-2-2-2-2-3-2-2	
	2630	2-2-2-2-2-2-3-2-3-1-2	
	2640	1-3-1-2-1-2-2-2-3-2	
	2650	2-4-8-5-4-6-2-5-6-5	
	2660	6-4-3-2-3-2-3-6-4-6	
	2670	6-5-5-6-4-7-7-6-6-5	
	2680	5-6-7-6-6-6-6-6-5-4	
	2690	4-7-5-6-4-4-4-6-5-7	
2690	2700	8-8-7-6-6-10-8-8-6-8	2700 - Trip
	2710	4-2-3-6-5-3-4-4-6-6	
	2720	7-5-7-4-6-5-4-6-7-6	
	2730	4-6-6-7-5-5-6-4-5-5	
	2740	4-4-4-4-6-7-6-6-2-4	
	2750	10-12-6-6-6-5-5-6-10-5	
	2760	7-7-9-10-8-7-5-6-4-4	
	2770	2-4-8-8-9-9-6-5-7-7	
	2780	7-6-9-7-7-8-7-7-9-6	
	2790	7-9-8-9-7-8-8-8-8-8	
2790	2800	9-7-9-8-9-9-10-9-7-5	
	2810	6-8-9-9-9-10-9-9-9-8	
	2820	9-9-8-5-4-10-9-7-9-7	
	2830	6-5-5-2-3-5-4-5-6-6	
	2840	6-6-5-5-5-3-4-5-7-8	
	2850	8-7-7-8-9-7-8-10-9-5	
	2860	7-6-8-8-8-8-10-9-8-9	
	2870	7-4-5-6-8-5-4-6-6-5	
	2880	6-5-6-8-9-8-9-8-9-9	
	2890	9-10-10-8-10-9-8-9-9-7	
2890	2900	9-7-7-8-8-10-10-6-6-5	2897 - Trip
	2910	6-5-6-3-5-3-4-4-2-1	
	2920	2-6-10-6-9-5-3-3-4-3	
	2930	3-4-2-2-2-3-4-4-4-6	
	2940	5-4-4-4-4-5-4-5-7-5	
	2950	5-4-4-3-4-3-2-3-2-3	
	2960	3-4-3-4-3-4-4-4-3-4	
	2970	4-4-4-4-4-4-3-3-4-4	
	2980	3-3-4-3-3-3-4-3-3-4	
	2990	4-4-4-5-3-5-4-5-5-4	
2990	3000	5-6-6-7-7-7-8-8-4-4	
	3010	4-4-4-4-5-4-5-6-4-4	
	3020	3-4-3-4-2-3-4-3-3-4	
	3030	5-4-5-5-5-4-3-3-4-4	
	3040	4-4-3-3-5-8-8-7-9-8	
	3050	8-8-5-5-5-3-6-6-6-6	
	3060	6-5-4-4-4-4-4-6-6-6	
	3070	5-4-4-4-5-7-8-7-9-7	
	3080	7-8-8-7-4-4-3-5-8-6	
	3090	8-7-8-7-7-8-5-5-5-5	
3090	3100	7-5-4-3-4-4-5-5-5-5	
	3110	4-5-5-4-5-5-5-4-3-4	
	3120	4-5-5-3-4-7-4-3-4-5	
	3130	6-4-6-6-5-5-6-6-5-5	
	3140	6-5-6-6-4-3-3-3-4-4	
	3150	6-6-5-5-3-3-4-4-3-2	
	3160	4-4-3-4-4-4-5-5-7-5	
	3170	6-6-8-5-6-7-7-7-7-6	
	3180	8-9-9-6-5-7-7-7-7-6	
	3190	7-5-3-4-4-4-4-4-4-3	
3190	3200	4-6-9-7-8-5-8-7-7-5	
	3210	7-5-5-5-4-5-6-5-5-4	
	3220	5-5-4-5-5-7-5-5-5-7	

3136-40 - S.R.  
3142 - Circ. 1 Hr.

15.009.04852.0000

WAYNE E. WALCHER

Consultant Geologist

CENTRAL BUILDING  
WICHITA, KANSAS

The Henderson Oil Company No. 5 Scheufler  
SE SE SE 16-20-11W, Barton County, Kansas

<u>From</u>	<u>To</u>	<u>Minutes</u>	<u>TIME LOG</u>	<u>Remarks</u>
3220	- 3230	5-6-5-5-3-2-3-4-5-6		
	3240	5-6-5-5-4-5-7-7-7-8		
	3250	4-4-4-4-4-4-5-5-4-6		3247 - S.R.
	3260	8-6-6-5-5-6-5-5-4-5		
	3270	5-5-5-5-5-5-5-7-5		
	3280	5-5-6-5-7-6-7-7-8-6		3280 - S.R.
	3290	6-5-5-4-5-4-4-4-4-5		3281 - S.R.
	3296	7-6-7-5-7-5		3296 - Circ. for Spks 1 Hr.
				3293 - Circ. Spks 1 Hr.
				3294 - S.R.