


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 22 Twp. 20 Rge. 10 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SW NE
Lease Owner R. D. Olson
Lease Name Woodmansee Well No. 3
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9-24-66 _____ 19____
Plugging completed 9-27-66 _____ 19____
Reason for abandonment of well or producing formation Depleted.



If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3395 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	180'	None
				5-1/2"	3394'	2394'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3395', sanded hole to 3380' and dumped 5 sacks of cement @ 3380' with dump bailer. Pulled 5 1/2" casing, set 10' rock bridge @ 180' and dumped 20 sacks of cement. Mudded hole to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1966

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1966

Milton J. John
Notary Public.

My commission expires May 20, 1968


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MUIR-THOMPSON, INC.
Farm- Woodmansee No. 3

SEC. 22 T. 20 R. 10W
NE SW NE

Total Depth, 3395'
Comm. 12-8-62 Comp. 12-19-62
Shot or Treated.
Contractor, Bea Drilling Co., Inc.
Issued. 3-16-63

County Rice
KANSAS



CASINO:
8" 180.56' cem w/135 sx.
5½" 3394' cem w/125 sx.

Elevation. 1832' RB

Production. 50 BOPD & 80% WTR,

Figures Indicate Bottom of Formations.

surface sand & shale	180
shale & shells	295
red rock & shale	470
anhydrite	505
red bed	880
shale & shells	1000
salt & shale	1300
shale & shells	1380
shale & lime	1575
lime & shale	2130
shale & lime	2365
lime & shale	2500
shale & lime	2637
lime & shale	2950
shale & lime	3095
lime & shale	3228
lime	3350
lime & shale	3395 RB
Total Depth	

TOPS: SCOUT	
Tarkio Sand	2340
Heebner	2900
Brown Lime	3040
Kansas City	2050
Arbuckle	2290

DST #1 2313-2365' Op 1 hr. Rec: Gas to surface in 3 min., gauged: 10 min. -1,020,000, 20 min. -1,020,000, 30 min. -802,000, 45 min. - spraying salt water. Rec, 120' hvy gas w/seo, 660' hvy gcmddy form. wtr. No ISEP taken, PSIP 735#/20 min., IFF 290#, FFP 290#.

DST #2 3348-3395' Good blow, Res, 1020' of HO & GCM. IFF 46#, FFP 381#, BIF 1023#.

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1966
CONSERVATION DIVISION
Wichita, Kansas