


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

## WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines 1/4 Sec. 22 Twp. 20 Rge. 12 (E) (W)  
Lease Owner Morris & Thompson Inc  
Lease Name Well Well No. 1  
Office Address 217 East 8th Topeka, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed Started to Plug 6-29 1965  
Application for plugging filed Yes 19    
Application for plugging approved Was 19    
Plugging commenced 6-30 1965  
Plugging completed 7-2 1965  
Reason for abandonment of well or producing formation Prod Depleted  
If a producing well is abandoned, date of last production 6-15 1964  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes  
Name of Conservation Agent who supervised plugging of this well Herman Justis  
Producing formation 3400 ark Depth to top 3390 Bottom    Total Depth of Well 3405 Feet  
Show depth and thickness of all water, oil and gas formations. 4 ft

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3405 feet to 3390 feet for each plug set. 8 sacks Cement 3390 to 3370

Mud from 3370 to 180 Rock Bridge from 180 to 170  
20 sacks Cement from 170 to 110. mud from 110. 35 ft  
Rock Bridge & 10 Cement to Base of Celler

RECEIVED  
STATE CORPORATION COMMISSION

JUL 26 1965

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Green & Smith  
Address Box 156 Eldridge Wood Kansas

STATE OF Kansas COUNTY OF Shawnee ss.  
James W. Thompson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

James W. Thompson  
217 E. 8th Topeka, Kan.  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of July 1965

My commission expires Sept. 10, 1968

Notary Public.

WILKINSON DRILLING, INC.  
805 Union Center Building  
Wichita 2, Kansas.

September 29, 1960

Gill # 1

Company: WILKINSON DRILLING, INC.  
Contractor: Company Tools  
Commenced: September 21, 1960  
Completed: September 28, 1960  
Total Depth: 3427'  
Location: SW NE NE, Section 22-20-10  
Rice County, Kansas.  
Elevation: 1836' Kelly Bushing, 1831' Ground Level  
Casing: 8 5/8" @ 182' W/150 sacks

FIGURES INDICATE BOTTOMS OF FORMATION

<u>DEPTH</u>	<u>FORMATION</u>
0 - 45	Surface Soil & Sand
45 - 186	Shale & Shells
186 - 195	Shale & Red Beds
195 - 480	Red Beds
480 - 510	ANHYDRITE
510 - 880	Red Beds
880 - 1520	Shale & Shells
1520 - 2000	Shale & Lime
2000 - 2100	Lime & Shale Streaks
2100 - 2150	Shale
2150 - 2170	Sand
2170 - 2190	Shale
2190 - 2250	Sand Stringers & Shale
2250 - 2310	Shale
2310 - 2342	Lime & Shale
2342 - 2360	Sand
2360 - 2484	Lime & Shale
2484 - 2530	Shale
2530 - 2630	Lime & Shale
2630 - 2730	Lime
2730 - 2908	Lime & Shale Streaks
2908 - 2914	HEEBNER Shell
2914 - 2939	Lime Shell
2939 - 3042	Silty Shale
3042 - 3326	Lime & Shale Streaks
3326 - 3332	Shale
3332 - 3340	Sand
3340 - 3346	Shale
3346 - 3356	Sand
3356 - 3384	Shale
3384 - 3392	Sand
3392 - 3427	ARBUCKLE DOLOMITE

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 3 1960  
CON. DIVISION  
Wichita, Kansas

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Gill #1, located in the SW NE NE, Section 22-20-10, Rice County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Wilkinson

Subscribed and sworn to before me this 30 day of September, nineteen hundred and sixty.

Carole H. Moore

My Commission expires January 2, 1961