

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 22 Twp. 20 Rge. 10 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW

Lease Owner Tomlinson-Kathol, Inc.

Lease Name Kelly Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__

Plugging commenced 1-16-64 _____ 19__

Plugging completed 1-18-64 _____ 19__

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3414 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	?	None
				5-1/2"	3411'	2892'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole to 3400' and dumped 5 sacks of cement @ 3400' with dump bailer. Pulled 5 1/2" casing, bailed hole to 170', set rock bridge and dumped 25 sacks of cement. Mudded hole to 30' and ran 10 sacks of cement to cap well.

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1964

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 1964

My commission expires May 20, 1964

Milton J. Volin
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
308 East Murdock, Wichita, Kansas


15.159.00078.0000

TOM KAT.
Company WEST SUPPLY COMPANY
Farm- Kelley No. 1

SEC. 22 T. 20 R. 10W
NE NE NW

Total Depth. 3414 RB
Comm. 1-6-53 Comp. 1-15-53
Shot or Treated.
Contractor. Pabco Drilling, Inc.
Issued. 2-28-53

County Rice
KANSAS



CASING:
8 5/8" 220'
5 1/2" 3411' cem w/75 sx

Elevation. 1848 ft.

Production. Pmp 80 bbls / 46%
water

Figures Indicate Bottom of Formations.

shale	0 - 305
red beds	480
anhydrite	500
redbeds, shale, shells	1005
shale, shells	1025
salt, shale	1260
lime, shale	1405
lime	1580
shale, lime	1720
lime	1845
lime, shale	2325
shale	2347
sand	2373
sand, shale	2470
shale, lime, sand	2560
lime	2623
lime, shale	2692
lime	2765
lime, shale	2875
lime	2929
shale, lime	3055
lime	3155
lime	3385
shale, sand	3409
lime	3414 RB
Total Depth	

Tops: R.B.
Indian Cave Sand 2367- 75
Howard 2550
Severy Sand 2615-2624
Topeka 2646
Heebner 2922
Brown Lime 3055
Lansing 3080
Simpson 3367
Arbuckle 3409

Drill Stem Test: 2337-2373,
open one hour, rec. 180'
slightly oil & gas cut mud,
125' salt water, BHP 610# in
20 mins.

2616-2623,
open 1 hour, rec. 50' oil cut mud,
60' salt water, BHP 710# in 20
mins.

3159-3176,
open 1 hr., rec. 15' mud, BHP
560# in 15 mins.

3402-3409,
open 1 hr, rec. 55' oil cut mud,
BHP 1010# in 15 mins.

3406-3414,
open 30 mins, rec. 600' oil,
HP (rig broke down & no record)

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1964

CONSERVATION DIVISION
Wichita, Kansas