


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Rice County. Sec. 22 Twp. 20E Rge. 10W (E) (W)

Location as "NE/CNW%SW%" or footage from lines. C W/2 NE NW

Lease Owner H. L. Herbel Production Company

Lease Name Kelley Well No. 2

Office Address Chase, Kansas - Box 506

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 20 1953

Application for plugging filed August 28 1953

Application for plugging approved August 31 1953

Plugging commenced August 31 1953

Plugging completed September 4 1953

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production XXXXXXXXXXXX 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruell Durkee

Producing formation XXXXXXXX Depth to top XXX Bottom Total Depth of Well 3427 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	water	3404'	3427'	8-5/8"	140'	None
				5-1/2"	3424'	2622'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from 3427' to 3400' and ran 6 sacks of cement which filled to 3340'. Mudded hole from 3340' to 135', set 10' rock bridge and ran 15 sacks of cement on bridge at 125'. Mudded hole to 35', set a rock bridge and ran 10 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
E. E. O'Brien (Employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. O'Brien

Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of September, 1953

My commission expires May 20, 1957

24-7868-8 3-53-20M

PLUGGING
FILE SEC 22 T 20 R 10W
BOOK PAGE 125 LINE 20

RECEIVED
STATE CORPORATION COMMISSION
SEP - 8 1953
9-8-53
CONSERVATION DIVISION
Wichita, Kansas

Contractors Well Log.

OPERATOR H.L. Herbel et al FARM NAME Kelley WELL NO 2
 Location C N/2 NE NW 20
~~SE NW NE~~ 22-18-10 COUNTY Rice STATE Kansas
 Commencement Date 7/27/53 Completion Date 8/6/53

LOG OF WELL

* ALL MEASUREMENTS FROM TOP OF ROTARY BUSHING

FROM	DEPTH TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	140	Surface soil		
140	480	Shale Shells		
480	495	Anhydrite		
495	960	Shale Shells		
960	1120	Salt		
1120	1230	Shale Shells		
1230	1640	Lime shale		
1640	1720	Lime shale(sandy)		
1720	2070	Lime shale		
2070	2362	Shale Shells		
2362	2382	sandy shale		
2382	2398	shale shells		
2397	2498	lime shale		
2498	2535	sandy shale		
2535	2651	lime shale		
2651	2929	lime		
2929	2934	shale		
2934	2962	lime		
2962	3051	lime shale sandy		
3051	3330	lime		
3330	3404	shale sand		
3404	3425	Arbuckle	Total Depth	3427'

Set 140' (5 joints) 8 5/8" casing - circ.
 Set 3424' (108 jts) 5 1/8" casing - 100 sax

STATE OF KANSAS)
 SS
 COUNTY OF RICE)

The undersigned certifies that to the best of his knowledge and belief the above facts are true and correct.

STAG DRILLING INC.,

BY G. L. Pyrell
 President


Subscribed and sworn to before me this 12th day of August 1953

My Commission Expires 3/1/55

Orlando Miller
 Notary Public

Perf 3402-3404 - squeezed

Perf 3401 - 3405'



RECORDS SECTION
 AUG 13 1953
 CONSERVATION DIVISION
 WASHINGTON, D.C.