


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rice County. Sec. 22 Twp. 20 Rge. 10 E/W
Location as "NE/CNW/SW" or footage from lines
NW NE NW

Lease Owner Estate of Icer Addis
Lease Name Madden Well No. 1
Office Address P. O. Drawer 8038 Wichita, Ks. 67208
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

dry hole
Date Well completed March 6, 19 81
Application for plugging filed March 6 19 81
Application for plugging approved March 6 19 81
Plugging commenced 4:00 P. M. March 6 19 81
Plugging completed 5:00 P. M. March 6 19 81
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3404'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

450' with 30 sx. Cement
250' with 30 sx. Cement
40' with 10 sx. Cement
5 sacks in rathole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

STATE OF Kansas COUNTY OF Barton, ss.
Don Popp (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Don Popp Holsington, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of march, 19 81.

Bessie M. DeWerff Notary Public.

My commission expires 5-20-81

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1981

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS WELL LOG

L. D. DRILLING, INC. - CONTRACTOR

ESTATE OF ICER ADDIS - OPERATOR

MADDEN # 1
NW NE NW
Sec. 22-20S-10W
RICE COUNTY, KS.

T. D. 3404'
ELEV. 1836 K.B.

COMMENCED: 3-1-81
COMPLETED: 3-6-81

CASING

8 5/8" set at 260'

CEMENT

W/250 sx. 50/50 Pozmix, 2% Gel, 3% CC

FORMATION

Sand	0 - 260
Red Bed	260 - 473
Anhy.	473 - 487
Shale & Shells	487 - 1300
Lime & Shale	1300 - 1770
Lime W/Shale	1770 - 3404

FORMATION TOPS:

Anhydrite	473-487
Grandhaven Lime	2233
Tarkio Lime	2316
Elmont Lime	2380
Topeka	2634
Heebner	2909
Toronto	2925
Douglas	2942
Brown Lime	3041
Lansing	3060
Base K/C	3332
Simpson	3358
Simp. Sand	3364-69
Simp. Sand	3372-76
Arbuckle	3400
R.T.D.	3404

STATE OF KANSAS)
COUNTY OF BARTON) ss

I certify that this is a true and correct copy of the above log to the best of my knowledge.

L. D. DRILLING, INC.

Don Popp
Don Popp

Sworn to and subscribed before me this 10th day of March 1981

My appointment expires: 5-20-81

Bessie M. DeWerff
Bessie M. DeWerff, Notary Public

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1981

CONSERVATION DIVISION
Wichita, Kansas