

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Durby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-22,058.0000

LEASE NAME Schartz

WELL NUMBER 1

1650 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 7 TWP. 20 RGE. 11 (E) or (W)

COUNTY Barton

Date Well Completed na

Plugging Commenced 2-22-93

Plugging Completed 2-22-93

LEASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd North Bldg. 300 Wichita, KS.67226

PHONE#(316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 22, 1993 (date)

by Bruce Basie (KCC District Agent's Name).

Is ACO-1 filled? na If not, is well log attached? no

Producing Formation ar buckle Depth to Top \_\_\_\_\_ Bottom T.D. 3330

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	302	8 5/8"	302	none
production		0	3326	4 1/2"	3326'	1770'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Shot 4 1/2" @ 1770' Pull 9 jts. to 1400' dump 150 sx., pull 17 more to 680' dump 75 sx., Pull 9 jts. to 320' dump 75 sx. and circulate cement to top. Pull rest of joints and dump 20 sx. down hole to fill to top. Plug down 3:45 PM Total 320 sx. 60/40 Poz, 6% Gel & 200# Hulls

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Saturn Well Service License No. 03641

Address R.R. 1 Box 183 B Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Barton, ss.

L. D. Davis (Employee of Operator) or (XXXXXXX) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. D. Davis

(Address) R.R. 1 Box 183 B Great Bend, KS.

SUBSCRIBED AND SWORN TO before me this 22nd day of February, 1993

My Commission Expires: 5-20-93

Bessie M. DeWerra  
NOTARY IN CORPORATION  
COMMISSION  
Bessie M. DeWerra



**FEB 23 1993**  
Form 0-1  
revised 05-80  
CONSERVATION DIVISION  
Wichita, Kansas