


WELL PLUGGING RECORD

Give All Information Completely  
Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 1 Twp. 20S Rge. 6 11 (W)  
Location as "NE/CNW<sup>1</sup>/<sub>4</sub>SW<sup>1</sup>/<sub>4</sub>" or footage from lines 330' SWL, 330' EWL, NW, NE, NE  
Lease Owner Gulf Oil Corporation  
Lease Name L. A. Steckel Well No. 7  
Office Address Box 661, Tulsa, Oklahoma.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed March 3, 19 36  
Application for plugging filed November 9, 19 51  
Application for plugging approved December 15, 19 51  
Plugging commenced December 24, 19 51  
Plugging completed December 24, 19 51  
Reason for abandonment of well or producing formation Not economical to produce.  
If a producing well is abandoned, date of last production November 8, 19 49  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough  
Producing formation Siliceous Lime Depth to top 3270' Bottom 3292' Total Depth of Well 3292' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	153'	0'
				7" OD	3269'	1637'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with sand from 3292' to 3260' and dumped six sacks of cement. Ripped casing at 2750', 2690', 2610', 2430', 2360', 2270', 2180', 2090', 2000', 1910', 1820', 1730' and 1640'. Mudded hole from top of cement to 160'. Set 10' rock bridge and dumped twenty sacks of cement. Mudded hole to 30' and set rock bridge and capped with ten sacks of cement.

RECEIVED  
DIVISION  
KANSAS  
12-31-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. S. G. Sanderson  
Address Gulf Oil Corporation Box 661, Tulsa, 2, Oklahoma

STATE OF KANSAS, COUNTY OF RICE, SS.  
H. H. Wright (employee of owner) by owner or operator of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. H. Wright  
P. O. Box 544, Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of December, 19 51

My commission expires April 14, 1952 AM Council Notary Public.

PLUGGING  
FILE SEC LT 20 R1W  
BOOK PAGE 124 INK 16

15.009.14257.0000

# WELL RECORD

WELL NO. **7** LEASE **L. A. Steckel** COMPANY **Gulf Oil Corporation Of Pennsylvania** AUTH. **K-2557**  
 DATE—Drilling Began **2-5-36** Well Completed **3-3-36** First Production **2-29-36**  
 SHOT—Date **Not shot** With Quarts—From To By  
 SAND RECORD **Siliceous Lime - 3270-1/2' to 3292'** Total Depth **- 3292'**  
 INITIAL PRODUCTION\* **"P" 1307 Oil, No water, (3/7)**

## CASING RECORD

Size	Wt.	Thd.	Class	Make	Run	Sacks Cement	Pounds Cal. Chlo.	Pulled	Left In
10"	40	10	SH	Lapw.St.	153'	90	270		153'
7"	OD 24	10	NEW	S. CHESTER Lapw.St.	3269'	100			3269'

S- 1 T- 205 R- 11W

Barton County, Kansas.

(\* Best Day; "F", Flowing Naturally; "L", Air-Gas Lift; "S", Swabbing; "P", Pumping.

Elevation - 1761'

ACIDIZED: 3-3-36 with 1000 gallons 50% solution.

3270' 1/2"  
 3292' TOTAL DEPTH

RECEIVED  
 STATE COMMISSION  
 NOV 14 1951  
 CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC-1-T-20-R-11W  
 BOOK PAGE 124 LINE 16

