

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barton

County. Sec. 1 Twp. 20 Rge. (E) 11 (W)

NORTH

Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines

Lease Owner Simon Lebow CorporationLease Name SteckelWell No. 4Office Address 607 Oil Capital Bldg., Tulsa, OklahomaCharacter of Well (completed as Oil, Gas or Dry Hole) oilDate well completed June 3 19 41Application for plugging filed Aug 12 19 65Application for plugging approved Aug 13 19 65Plugging commenced August 12 19 65Plugging completed Sept. 1 19 65Reason for abandonment of well or producing formation not commercialIf a producing well is abandoned, date of last production 6-1 19 65Was permission obtained from the Conservation Division or its agents before plugging was commenced? YesName of Conservation Agent who supervised plugging of this well Don TruinProducing formation Depth to top Bottom Total Depth of Well 3277 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	135'11"	none
				5 1/2"	3268'	181.15'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back in the 5" with gravel and dumped 5 sacks of cement. Shot pipe off at 181', as well had been squeezed. Pulled pipe and mudded hole to 181'. Set rock bridge and finished filling surface with 5 yards of ready mix cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self
Address Hutchinson, Kans.STATE OF Kans., COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Bert Self
R. R. #4, Hutchinson, Kans.

(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of September 19 65My commission expires October 15, 1965

Notary Public.


WICHITA BUREAU - KANSAS GEOLOGICAL SOCIETY.
4-- Union National Bank Bldg, Wichita, Kansas.

C.H. LEBOW
Emma Stockel No. 4

SEC. 1 T. 20 R. 11W.
CWL NE SW

Total Depth. 3277
Comm. 5-19-41 Comp. 6-3-41
Shot or Treated.
Contractor. E.K. Carey
Issued. 7-26-41

County Barton.



CASING.

85/8 135' 11" Cem.
5 1/2" 3268' Cem.

Elevation.

Production. Pot. 1123 B.

Figures Indicate Bottom of Formation.

surface clay	8
sand	100
shale	107
sholl	110
shale	125
shale grey	134
red bed	480
shale and shells	780
shale and shells	1010
salt and shells	1129
shale & red bed	
lime	1320
broken lime	1497
sdv limo & shale	1625
limo	1642
sand rough soft	1677
limo and sand	1705
limo	2080
broken limo	2217
limo and shale	2380
shale sticky	2406
limo	2467
shale and limo	2477
broken limo	2618
limo	2710
shale and limo	2726
limo hard	2765
shale and limo	2984
shells and limo	2988
broken limo	3034
limo	3213
shale and limo	3226
limo	3235
limo and iron	3264
shale	3266
Arbucklo	3270
limo	3277
Total Depth.	

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1965
CONSERVATION DIVISION
Wichita, Kansas