

15.159.30059.0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Stickney #1

WELL NUMBER _____

SPOT LOCATION SE NE NESEC. 11 TWP. 20 RGE. 10W (E) or (W)COUNTY Rice

Date Well Completed _____

Plugging Commenced 1/17/85Plugging Completed 1/23/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Paul Bandy Oil ProducerADDRESS Box 364, Canton, Ks. 67428PHONE # (316) 628-4417 OPERATORS LICENSE NO. 5990

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YesWhich KCC/KDHE Joint Office did you notify? Salina

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3355'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	210'	none
				5 1/2"	3354'	2185'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 3240' & 5 sacks cement. Shot pipe at 2613', 2418', & 2185'. Pulled 54 joints of pipe. Pumped well with 400# hulls, 20 sacks gel, 100# hulls, & 100 sacks 50/50 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss. **RECEIVED**
STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) or JAN 25 1985
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God. **CONSERVATION DIVISION**
Wichita, Kansas

(Signature) R. Darrell Kelso(Address) Box 347, Chase, ks. 67524SUBSCRIBED AND SWORN TO before me this 24th day of January, 1985

My Commission expires: _____



Irene Hoover
Notary Public