

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800-Bitting Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Rice County. Sec. 10 Twp. 20S Rge. XELOW (W)
Location as "NE/CNWSW" or footage from lines 990' fr. N, 330' fr. W, NW/4
Lease Owner Phillips Petroleum Company
Lease Name Taylor "D" Well No. 2
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 17 19 56
Application for plugging filed April 17 19 56
Application for plugging approved April 18 19 56
Plugging commenced April 17 19 56
Plugging completed April 17 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee
Producing formation Dry Hole Depth to top _____ Bottom _____ Total Depth of Well 3475 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Dry	2932	2955	9-5/8"	325.85 OA	None
Toronto	Dry	2955	2965			
Douglas	Dry	2965	3058			
Brown Limestone	Dry	3058	3077			
Lansing-Kansas City	Dry	3077	3342			
Marmaton	Dry	3347	3374			
Conglomeratic Sand	Dry	3374	3431			
Arbuckle	Dry	3431	3475			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole from 3475' to 250'. Set Halliburton wood plug with 1/3 sack Hulls on top at 250'. Ran drill pipe to 240', dumped 20 sx. cement. Mudded hole to 20'. Set Howco plug at 20' and dumped 1/3 sack hulls on top. Dumped 5 sx. cement in filling to base of cellar. Well Plugged and Abandoned at 5:30 P.M. 4-17-56.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Phillips Petroleum Company
Address Oklahoma City, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.
A. J. Willis (employee of owner) ~~not a conservator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. J. Willis
Box 779, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of April, 19 56.

My commission expires November 18, 1957

Joseph M. Breal
Notary Public.

PLUGGING
FILE SEC 10 T 20 R LOW
BOOK PAGE 54 LINE 15

APR 21 1956
4-20-56
CONSERVATION DIVISION
Wichita, Kansas

EXPLORATION RECORD

PHILLIPS PETROLEUM COMPANY - Taylor "D" #2 - 990' from North and
 330' from West Lines, NW/4 Sec. 10-20S-10W
 Rice County, Kansas.

Lease Taylor "D"

Well 2

Formation Name	Top	Base	Remarks
Clay, sand and redbed	0	320	
Redbed and shale	320	476	
Shale	476	554	
Shale, shells and salt	554	1335	
Lime and shale	1335	1887	
Lime	1887	2009	
Lime and shale	2009	2658	
Lime	2658	2903	
Lime and shale	2903	3082	
Lime	3082	3175	
Lime and chert	3175	3239	
Lime	3239	3365	
Lime and chert	3365	3398	
Chert, sand, quartz and shale	3398	3404	
Lime	3404	3475	

FORMATION TOPS: (SAMPLE)

Heebner	2932
Toronto	2955
Douglas	2965
Brown Limestone	3058
Lansing-Kansas City	3077
Drum	3225
Base-Kansas City	3342
Marmaton	3347
Conglomeratic Sand Zone	3374
Arbuckle	3431
Rotary Total Depth	3475

PLUGGING
 FILE SEC 10 T 20 R 10W
 Form 20333 PAGE 54 LINE 15

APR 1954