


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

**WELL PLUGGING RECORD**

Rice County. Sec. 10 Twp. 20S Rge. (E) 10 (W)

Location as "NE/CNW/SW" or footage from lines NW NE NW  
Lease Owner Phillips Petroleum Co.  
Lease Name Taylor "E" Well No. 1  
Office Address Box 287 - Great Bend, Kans.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed April 16 19 56  
Application for plugging filed May 23 19 63  
Application for plugging approved June 3 19 63  
Plugging commenced June 14 19 63  
Plugging completed June 20 19 63  
Reason for abandonment of well or producing formation Unprofitable to operate



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production May 13 19 63  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation Conglomerate Depth to top 3356 Bottom \_\_\_\_\_ Total Depth of Well PE3385 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	TOP	TD	SIZE	PUT IN	PULLED OUT
LKC	Oil show	Top 3052		9-5/8"	321.24' OA	None
Marmaton	Oil show	Top 3326		7 "	3423.13' OA	1812'
Conglomerate	Oil	Top 3356				
Arbuckle	Oil show	Top 3395				
Simpson sand	Oil show	Top 3392				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped sand 3385' to 3240' & 6 sacks cement 3240' to 3175'.  
Shot off and pulled 7" casing. Mudded to 300', set wood  
plug and rock bridge 300' to 290', dumped 30 sacks cement  
to 225', mudded to 30', and dumped 30 sacks cement to surface.

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 24 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Forbes Casing Pulling Co.  
Address Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
J. M. Beck, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. M. Beck, Jr.  
Box 287 - Great Bend, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of June, 19 63

My commission expires Nov. 18, 1965 Joseph M. Beck Notary Public.

15.159.04287.0000

FORMATION RECORD

Taylor "E" #1 (NW NE NW Sec. 10-20S-10W)

0	195	Sand & shale
195	319	Sand, shale & shells
319	432	Redbed & anhydrite
432	1355	Shale & shells
1355	1693	Lime & shale
1693	1842	Lime
1842	2533	Lime & shale
2533	2906	Lime
2906	3023	Lime & shale
3023	3343	Lime
3343	3390	Lime & sand
3390	3400	Lime

RECEIVED  
STATE CORPORATION COMMISSION

JUN 24 1963

CONSERVATION DIVISION  
Wichita, Kansas