


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Rice County, Sec. 13, Twp. 20S, Rge. (E) 10 (W)
Location as "NE/CNW/SW" or footage from lines G W/2 E/2
Lease Owner Ben C. W. Hyde, Jr.
Lease Name Miller Well No. 4
Office Address 4722 Broadway, Kansas City 12, Missouri
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed October 13, 1966 19____
Application for plugging approved _____ 19____
Plugging commenced October 21, 1966 19____
Plugging completed November 12, 1966 19____
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3340 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	152'	8 5/8"	152'	none
		0	3338'	5 1/2"	3338'	1493.45

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 3325', set 10' rock bridge and dumped 5 sacks of cement at 3315'.

Pushed plug to 152'. Set 10' rock bridge. Mixed 4 sacks of cement with 10# of calcium chloride and dumped on bridge. Let set over week-end. Bail hole down and dump 21 sacks of cement. Fill hole with mud to 40', set 10' rock bridge and cap hole with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Dean Wells (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Dean Wells*
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 1966.

George A Meyer
Notary Public.

My commission expires Feb. 10, 1967

15.159.04455.0000
 WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
 412 Union National Bldg. Wichita, Kansas


COPY

Company: BEN C. HYDE, JR.
 Farm: Miller No. 4

SEC. 13 T. 20 R. 10W
 QWL E $\frac{1}{2}$ SE

Total Depth. 3340'
 Conn. 4-4-48 Comp. 4-21-48
 Shot or fringed.
 Contractor: Mallard Drlg. Co.
 Date: 7-17-48

County: Rice
 KANSAS



CASING:
 8-5/8" 152' Cem. W/135 Sx.
 5-1/2" 3336' Cem. W/ 75 Sx.

Elevation: _____
 Production, Est. 15 Bbls.

Figure indicates Bottom of Formations.

surface sand	152
red shale & shells	290
red bed	310
shale & shells	1175
shale & lime	2570
lime	2670
lime & shale	2795
lime	2855
lime & shale	2985
lime & shale	3030
lime	3316
Simpson shale RTD	3336 $\frac{1}{2}$
Simpson Shale	3340
Total Depth	

Top Simpson Sand 3336

Measurements taken from top
 of derrick floor.

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 6 1966
 CONSERVATION DIVISION
 Wichita, Kansas