

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 124-16

LOCATION NW. 22E. 21E

SEC. 1 TWP. 20 RGE. 11-~~W~~

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 7 Lease L. A. Steckel

Operator Gulf Oil Corp. Address Box #661 Tulsa, Okla.

Field _____ County Barton

Total Depth 3292 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 155 ft. Cemented with 90 sacks of cement.
7 casing rot at 3269 ft. 100 sacks of cement. Plugged
back to 3260 ft with shot. Drilled 6 sacks of cement
at 3260 ft. Drilled off & pulled to 7 casing - mud
to 166 ft. Set Rock Bridge & 10 sacks of cement
at 166 ft mud to 30 ft. Bridge & 10 sacks of
cement at the surface.
Shull Casing Plugging Co. - Plugging Contractor

PLUGGING
FILE SEC 1 T 20 R 11 W
BOOK PAGE 124 LINE 16

DEC 28 1951
C. H. Stouffer
District Conservation Agent

Date 12-28-51