

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. ✓

LOCATION SW~~4~~

SEC. 1 TWP. 20 RGE. 11

Dry Hole — Abandoned Oil Well yes Abandoned Gas Well —

I have today completed supervision of plugging of:

Well No. 7 Lease Struckel

Operator Courtney D Davis Address Wichita Kans

Field — County Barton

Total Depth 3267 Feet.

(Describe briefly the manner in which the well was plugged)

The hole was plugged back 3267 ft to
3234 ft Lane Plug & Cement. Chertrock 3234 ft to 3085 ft
Cement 3085 to 3050.5 max. Heavy mud 3050
ft to 108 ft. Cement 108 ft to 78 ft. 20 max. Mud
78 ft to 10 ft Cement into cellar base.
10 max. 105 ft of 12 1/2 pipe cemented & left
in hole

H. W. Kern
District Conservation Agent

Date Oct 9 - 46

PLUGGING
FILE SEC-1 T-20 R-11 W
BOOK PAGE 75 LINE 35

