


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 41-34

LOCATION NE-SE-SE

SEC. 1 TWP. 20 RGE. 11W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 6 Lease Steckel

Operator Mr. Courtney B. Morris Address 7321 N.M. Beach Blvd. Wichita Kansas

Field \_\_\_\_\_ County Barton

Total Depth 3284 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 1 1/2 - 110 ft. Circulated with cement.  
7" casing set at 3273 ft. Plugged back to 3080 ft  
with cement - Four Wells Plug & Chat. Dumped 6 sacks  
of cement at 3080 ft - Shot off & Pulled the 7" casing  
Upld to 150 ft. Set Rock Bridge & 25 sacks of cement  
at 150 ft. Upld to 30 ft - Bridge & 10 sacks of  
cement at the surface.  
Bill Morgan - Plugging - Contractor

MAY 16 1951

STATE CORPORATION  
COMMISSION

Carl Stough  
District Conservation Agent

Date 5-13-50

**PLUGGING**  
FILE SEC 1 T 20 R 11W  
BOOK PAGE 4 LINE 34