

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE NE NE

SEC. 1 TWP. 20 RGE. 11

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Steckel

Operator Gulf Oil Corp. Address Chase, Kans

Field Silica County Barton

Total Depth 5275 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 150' circulated with cement - 7" at 3258'

with 80 sax cement behind.

Lane Wells. Plugs and cement to 5004', perforations at

5025' - filled with chat to ~~3000~~ 5000', set 6 sax cement

with dump bailer, pulled 7", filled hole with mud to 200',

set rock bridge and 20 sax cement - filled with mud to

50', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1951

CONSERVATION DIVISION
Wichita, Kansas

J. C. [Signature]
District Conservation Agent

Date 5-13-51

PLUGGING
FILE SEC 1 T 20 R 11 W
BOOK PAGE 88 LINE 33