

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE SE NE

SEC. 1 TWP. 20 RGE. 11

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 6 Lease _____ Steckel

Operator Gulf Oil Corp Address Chase, Kans

Field _____ County Barton

Total Depth 3270 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 156' circulated with cement - 7" at 3256'

Lane Wells plugs rock and cement to 3000', set 6 sax cement
at 3000' with dump bailer, pulled 2550' 7", filled hole with
mud to 200', set rock bridge and 20 sax cement, filled with
mud to 50', set rock and 10 sax cement. to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1951
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC LT 20 R 11 W
BOOK PAGE 88 LINE 25

District Conservation Agent
Date 5-8-51