

40 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1962
11-13-62
CONSERVATION DIVISION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Ben C. W. Hyde, Jr.

Complete Address: 4722 Broadway, Kansas City 12, Mo.

Lease Name Macemore Well No. 3

Location SE NE SE Sec. 11 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 3114'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Inc.

Address: 1809 Lakin, Great Bend, Kansas License No. 462

Operation Completed: Hour 11 AM Day 6 Month November Year 1962

The Above well was plugged as follows:

Hole filled with sand to 3050' and cemented with 4 sacks.

Hole filled with mud to 195'. Rock bridge set from 195' to 185' and

cemented with 25 sacks. Hole filled with mud to 30'. Rock bridge

set from 30' to 20' and hole cemented to bottom of cellar with

10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Willard J. Tomlin
Well Plugging Supervisor

DATE 11/13/62
INV. NO. ~~5000~~ 6006-W