

96 KANSAS STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts Assitant Director 500 Insurance Building 212 North Market Wichita 2, Kansas

RECEIVED STATE CORPORATION COMMISSION

JUN 21 1963

CONSERVATION DIVISION Wichita, Kansas

Operator's Full Name Phillips Petroleum Co.,.

Complete Address: Box 287 Great Bend, Kansas.

Lease Name Taylor Well No. I "E"

Location NW NE NW Sec. 10 Twp. 20 Rge. 10 (E) (W)

County Rice Total Depth 3400'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Co.

Address: Box 287 Great Bend, Kansas. License No. 49

Operation Completed: Hour 3:20PM Day 19 Month 6 Year 63

The Above well was plugged as follows:

Filled hole w/ sand from T.D. 3400' back to 3396' ran 7 sax cement w/ dump bailer.

Shot off 7" and pulled 7" casing. Filled hole w/ mud from 3400' back to 220' set a

10' rock bridge from 220' back to 210' ran 30 sax cement from 210' back to 150'.

Filled hole w/ mud from 150' back to 25'. Ran 10 sax cement from 25' back to zero 8'

below ground level. 10 3/4" surface pipe 8' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/21/63

INV. NO. 7298-W

Signed: [Signature] Well Plugging Supervisor