

STATE OF KANSAS
STATE CORPORATION COMMISSION
1 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-009-22,059-00-00

LEASE NAME Schartz "A"

WELL NUMBER 1

3960 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 7 TWP. 20 SRGE. 11W (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 4-3-02

Plugging Completed 4-4-02

RECEIVED

APR 24 2002

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd. St. North Bldg. 300 Wichita, Ks. 67226

PHONE (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

Patrick Staab (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3334

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	306'	None
				5-1/2"	3330'	2210'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each side. Plugged off bottom with sand to 3250' and 5 sacks cement. Shot pipe @2400' and 2210'. pulled up to 1350', pumped 95 sacks cement and 300# hulls, pulled up to 575', pumped 40 sacks cement and 100# hulls, pulled up to 250' and circulated 45 sacks cement to surface. Topped off with 20 sacks cement, 60/40 pos, 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of April, 2002

Irene Herzberg
Notary Public

My Commission Expires: _____



OR