

Orig - State Corp. Comm.  
Copy - B. A. Conner - 357 FPB  
Copy - Mary Crump - Okla City  
Copy - Well file

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barton SEC. 7 TWP. 20 RGE. 11 E/W  
Location as in quarters or footage from lines:  
C E/2 SW NE

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Locate Well  
correctly on above  
Section Platt.

Lease Owner Phillips Petroleum Company  
Lease Name Petz Well No. 2  
Office Address Box 287, Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole): oil  
Date Well Completed April 27, 1940  
Application for plugging filed Extended 8-3-82  
Plugging commenced 8-11-82  
Plugging completed 8-12-82  
Reason for abandonment of well or producing formation

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt *Schick*  
Producing formation Arb Depth to top 3315 bottom 3332 T.D. 3332  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

| Formation  | Content   | From | To    | Size   | Put in | Pulled Out |
|------------|-----------|------|-------|--------|--------|------------|
| Surface    | Water     | 0'   | 233'  | 8 5/8" | 231'   | -0-        |
| Production | Oil & Wtr | 0'   | 3315' | 5 1/2" | 3332'  | 340'       |
|            |           |      |       |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. On 8-11-82 MIRU Kelso Csg. Pullers & dump 5 sx cmt on bridge @ 2400'. Pulled 16" stretch on pipe and shot @ 2379'. Casing parted @ 340'. COOH w/14 its 5 1/2" csg. RDMO Kelso. MIRU Sun Cmtg & plug 8 5/8" csg as follows: 4 sx hulls, 12 sx gel, 70 sx 50-50 Poz, 3 sx gel, 1 sk hulls, 8 5/8" wiper plug & 60 sx 50-50 Poz. ISTP 1000#. RDMO Sun Cmtg. Weld plate on 8 5/8". Well P&A 8-12-82


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pullers, Inc.  
Chase, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
C. D. Dohrer (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) C. D. Dohrer Area Mgr.  
Box 287, Great Bend, Kansas 67530  
(Address)

Velma L. Mog Public.  
Velma L. Mog  
STATE CORPORATION COMMISSION



SUBSCRIBED AND SWORN TO before me this 15th day of August, 19 82  
My Commission expires: February 15, 1984

AUG 17 1982  
CONSERVATION DIVISION  
Wichita, Kansas