


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 7 Twp. 20S Rge. 11W (E) (W)

Location as "NE/CNWxSWx" or footage from lines. SW NE NE

Lease Owner Phillips Petroleum

Lease Name Petz Well No 5

Office Address Box 287, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole.

Date well completed 7-16-63 19

Application for plugging filed 7-16-63 19

Application for plugging approved 7-18-63 19

Plugging commenced 7-29-63 19

Plugging completed 7-31-63 19

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Donald Truan

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Top LKC	dry	3080		10-3/4	320	none
Base LKC	dry	3318		7"	3430	1741'
Arb.	dry	3335				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PTD 3240. Plugged back 3308 to 3260 with sand - dumped 5 sx cement to 3240'.

Shot 7" at 2670, 2541, 2187 and 1730. Pulled 57 jts 1741' of 7" OD csg.

Pumped 15 sx Jel down 10-3/4" csg followed with 100 sx common cement by Howco.

MP 500#. Well P& A 10 a.m. 7-31-63.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 5 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Csg Pull Unit

Address E 10th, Great Bend, Kan

STATE OF Kansas, COUNTY OF Barton, ss.

M. E. Michael Dist. Supt (employee of owner) or owner or operator of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. E. Michael

Box 287, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of August, 1963

My commission expires 11-18-65

Joseph W. Reed

Notary Public.



# WELL LOG

15.009.05201.0000

COMPANY Phillips Petroleum Co.

SEC. 7 T. 20S R. 11W

FARM Petz NO. 5


LOC. SW NE NE

TOTAL DEPTH 3409'

COUNTY Barton

COMM. 6-22-63 COMP. 6-29-63

CONTRACTOR Garvey Drilling Company



CASING 10 3/4" @ 320' w/100 sx

7" @ 3408' w/110 sx

ELEVATION 1785' DF

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 65' Surface Soil and Sand
- 245' Shale
- 280' Red Bed and Shale
- 324' Shale and Shells
- 535' Red Bed and Shale
- 560' Anhydrite
- 1385' Shale and Shells
- 1500' Lime and Shale
- 1955' Lime
- 2050' Lime and Shale
- 2170' Shale
- 2680' Shale and Lime Streaks
- 2705' Shale and Lime
- 2795' Lime
- 3065' Lime and Shale
- 3070' Brown Lime
- 3083' Shale
- 3305' Lime
- 3320' Lime and Shale
- 3385' Arbuckle
- 3409' Lime
- 3409' RTD

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 5 1963

CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas }  
County of Barton } ss

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Petz #5 well.

Subscribed and sworn to before me this 11th day of July 19 63

My Commission Expires: October 24th, 1966

Sam N. Stephens  
Notary Public