


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County. Sec. 7 Twp. 20 Rge. (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines CEL - SE - NW
Lease Owner Francis Oil & Gas, Inc.
Lease Name Schartz "A" Well No. 3
Office Address Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 11-14 1956
Plugging completed _____ 11-18 1956
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		6	310	8 5/8"		
		0	3325	5 1/2"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3335 to 3315 - dumped 5 sks cement - pulled pipe - pumped in 25 sks dellmud and 75 sks cement - let set over night - checked cement - down 46' - filled with cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 - 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Company License 236
Address Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Francis Oil & Gas, Inc (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Foster

SUBSCRIBED AND SWORN TO before me this 30th day of November, 1956

My commission expires _____
EVELYN L. DEVORE, NOTARY PUBLIC
MY COMMISSION EXPIRES MARCH 21, 1959
Notary Public.

PLUGGING
FILE SEC. 7 T. 20 R. 11W
BOOK PAGE 116 LINE 6

C. E. ASH ET AL
 P. Schartz A #3
 CEL SE NW Sec.: 7-20-11
 Barton County, Kansas

Comm. Rig Up : 1-20-43	Elevation :
Comm. Drlg. : 1-23-43	Initial Prod. : 62 Bbls.
Completed : 2-19-43	Contractor : C. E. Ash
Total Depth : 3335'	Tools : Rotary

CASING RECORD
Pulled

<u>Run</u>	<u>Left In</u>
310' 8-5/8" Surface	310' 8-5/8" Surface
3325' 5-1/2" O D	3325' 5-1/2" O D

<u>STRATA</u>	<u>DEPTH</u>
Sand	70
Shale	100
Iron & Lime	108
Shale & Shells	210
Sand	223
Shale	233
Shale & Shells	312
Red Shale & Sand	540
Anhydrate Lime	564
Shale	786
Shale & Shells	1060
Salt	1338
Shale & Shells	1350
Lime with Shale Breaks	1490
Lime	1915
Shale	1925
Lime	1928
Lime & Shale Breaks	1940
Shale	1995
Lime Broken	2015
Shale & Shells	2029
Lime	2060
Shall & Lime Shells	2260
Lime	2275
Shale & Shells	2395
Shale	2425
Lime	2450
Shale & Shells	2547
Shale & Lime	2632
Lime	2646
Shale	2680
Lime & Shale Breaks	2725
Lime	3010
Shale & Shells	3070
K.C. Lime	3324
Silicious Lime	3335
Total Depth	3335

I hereby certify that the above is the true and correct log of said well as reflected by the daily drilling reports.

C. E. ASH

Subscribed in my presence and sworn to before me this 6th day of April, 1943.

My commission expires April 15, 1946.

PLUGGING	
FILE SEC. <u>7</u> T. <u>20</u> R. <u>11W</u>	
BOOK PAGE <u>116</u> LI. E. <u>6</u>	

Notary Public in and for Sedgewick County, Kansas.
 CORPORATION COMMISSION
 NOV 14 1956
 REGISTRATION DIVISION
 Wichita, Kansas