

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit

Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 7 Twp. 20 Rge. 11 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines 300'S & 660'W of C of SE SE

Lease Owner Texaco, Inc.

Lease Name F. Petz

Well No. 4

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed \_\_\_\_\_ 19\_\_

Application for plugging approved \_\_\_\_\_ 19\_\_


Plugging commenced 3-22-65 \_\_\_\_\_ 19\_\_

Plugging completed 3-24-65 \_\_\_\_\_ 19\_\_

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Don Truan

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3322 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	282'	None
				7"	3298'	258'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, sanded hole to 3125' and dumped 5 sacks of cement @ 3125' with dump bailer. Pulled 7" casing, set rock bridge from 240' to 230' and dumped 20 sacks of cement @ 230'. Mudded hole to 30' and ran 15 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

APR 8 1965

4-8-65

PLUGGING COMPLETE.

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight

(employee of owner) or (OWNER/OPERATOR) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) \_\_\_\_\_

Noel J. Knight

Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of April, 1965

Milton J. Volin

Notary Public.

My commission expires May 20, 1968

# LOG OF WELL

SHEET NO. 2

District **Kansas**

Owner **The Texas Company** Farm **F. Potts**

Well No. **4**

FORMATION	BOTTOM	AMOUNT	COLOR	HARD or SOFT	DEPTH CORES TAKEN	REMARKS	
Surface	282	282				10-3/4" OD 40/LM Casing Set @ 282'	
Red Beds	680	598					
Salt	1206	528					
Shale	1320	112					
Shale & Shells	1490	170					
Lime	1520	30					
Shale & Shells	2703	1183					
Lime	2940	237					
Shale & Shells	3050	110					
Lime	3294	244					
Shale	3298	4					
Lime	3315	17					
Drilled to 3315 and acidized w/ 3000 Gallons Acid Then drilled 7 feet deeper to TD of 3322'							
Lime	3322	7					Top Arbuckle 3298'
<b>Total Depth</b>	<b>3322</b>						

10-7-40 (first acid) acidized w/ 1000 gal. Morgan  
no results

10-8-40 (2nd acid) acidized w/ 2000 gal. Morgan  
no results

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 1 1940  
CONSERVATION DIVISION  
TOPEKA, KANSAS