

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barton County, Sec. 7 Twp. 20S Rge. 11W (E) (W)

Location as "NE/CNW/SW" or footage from lines CW/2 SW SE

Lease Owner The Texas Company

Lease Name F. Petz Well No. 6

Office Address 614 Bitting Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed May 1 19 41

Application for plugging filed August 30 19 51

Application for plugging approved August 31 19 51

Plugging commenced September 8 19 51

Plugging completed September 9 19 51

Reason for abandonment of well or producing formation
Ceased to be a commercial producer

If a producing well is abandoned, date of last production January 19 51

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Arbuckle Depth to top 3311 Bottom 3339 Total Depth of Well 3339 Feet
3098 PBTB

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-1/4"	275	0
				5-1/2"	3311	2425

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED AS FOLLOWS:

- 3098-3060 - Sand
- 3060-3030 - 5 Sacks Cement
- 3030-275 - Heavy Mud
- 275-265 - Rock Bridge
- 265-225 - 15 Sacks Cement
- 225-30 - Heavy Mud
- 30-Bottom of Cellar - 10 Sacks Cement

RECEIVED
STATE CORPORATION COMMISSION
SEP 12 1951 9-12-51
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor R & S Pipe Pulling Company
Address Ellinwood, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
R. M. Acher (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *RMA*

614 Bitting Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of September, 19 51

My commission expires September 20, 1952 *J. Howard Kistler* Notary Public.

PLUGGING
FILE SEC 7 T 20 R 11W
BOOK PAGE 406 LINE 33

COPY
LOG OF WELL

Form PO-214 Sheet 1 (3-47)20M

F. PETZ NO. 6

15009-14384.0000

SHEET 1

OWNER The Texas Company DIVISION Oklahoma DATE MADE 5-19-41
 DISTRICT Kansas LEASE F. Petz WELL NO. 6
 STATE Kansas COUNTY OR PARISH Barton TWP. 20S RANGE 11W SEC. 7
 LOCATION OF WELL C W/2 SW/4 SE/4

COMMENCED RIGGING UP 4-13-41 COMMENCED DRILLING 4-15-41 COMPLETED DRILLING 5-1-41
 DAY DRILLER _____ NIGHT DRILLER _____ CONTRACTOR Helmrich & Payne Inc.
 CABLE FROM 3311 TO 3339 ROTARY FROM 0 TO 3311 COMPANY RIG No. _____
 TOTAL DEPTH 3339 MEASURED BY M. C. Harrell ELEVATION 1784

CASING RECORD

SIZE	WEIGHT	PUT IN WELL		PULLED OUT		LOST IN WELL		SHOES		PACKERS		
		FEET	INS.	FEET	INS.	FEET	INS.	LENGTH	MAKE	KIND	LENGTH	SET AT
8-1/4"	28# LW	275										FT.
5-1/2"	17# SS	3311										FT.
												FT.
												FT.
												FT.
												FT.
												FT.
8-1/2"	casing set at 275 w/250 sacks											FT.
5-1/2"	casing set at 3311 with 200 sacks											FT.

WAS CASING CEMENTED? _____ IF SO, HOW MANY SACKS OF CEMENT USED? _____
 LINER: STATE SIZE AND WEIGHT _____ WHERE SET _____ FT. AND INS. BLANK _____ FT. AND INS. PERFORATED _____
 HOW PUT TOGETHER _____ COUPLING _____ FLUSH-JOINT _____ INSERTED _____
 REMARKS: _____

EQUIPMENT RECORD

TUBING				SUCKER RODS			PUMPING OUTFIT
SIZE	WEIGHT	FEET	INS.	FEET	INS.	SIZE AND KIND	DESCRIPTION, KIND, SIZE, ETC.

FLOWING, PUMPING, GASSER OR DRY Pumping PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____
 IF GAS WELL, OPEN FLOW CAPACITY _____ SHUT IN PRESSURE _____ ROCK PRESSURE _____
 KIND OF SHOT _____ SIZE OF SHOT, QUARTS _____
 NUMBER OF SHELLS _____ SIZE OF SHELLS _____ INCHES, DIAMETER _____
 LENGTH OF SHELLS _____ FEET _____ INCHES _____ TOP OF SHOT _____
 BOTTOM OF SHOT _____ ANCHOR _____ WELL BRIDGED TO _____
 TOTAL DEPTH OF WELL _____ NUMBER OF SHOT _____ PRODUCTION BEFORE SHOT _____ BBLs. PER DAY _____
 PRODUCTION AFTER SHOT _____ BBLs. PER DAY. SHOT FURNISHED BY _____
 NAME OF SHOOTER _____ SHOT INSPECTED _____ BY SEP 12 1951
 COMMENCED DRILLING DEEPER _____ COMPLETED _____ CONS. DRILLING DEEPER
 TOTAL DEPTH _____ PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____

REMARKS: No Acid
Swabbing Test 120 bbls. oil - Established min. well

NOTE: IF WELL WAS DRY, STATE UNDER REMARKS, WHEN, HOW, AND BY WHOM PLUGGED.
 STATE UNDER REMARKS ANYTHING OF INTEREST, NOT COVERED IN LOG.
 IF THE SPACE PROVIDED FOR REMARKS IS NOT SUFFICIENT WRITE ON BOTTOM OF LAST SHEET OF LOG.

PLUGGING
 FILE SEC 7 T 20 R 11W
 BOOK PAGE 106 LINE 33

TOTAL NUMBER OF SHEETS 2

COPY

15.009.14384.0000

Form FO-214 Sheet 2 (7-44) 24M

LOG OF WELL

SHEET No. 2

District Kansas Owner The Texas Co. Farm F. Petz Well No. 6

FORMATION	AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
Surface Loam & Sand	60				
Shale & Shells	150 90				
Shale & Red Bed	252 102				
Red Bed Sh. & Sand	434 182				
Red Bed & Shells	534 100				
Shale & Shells	870 336				
Anhydrite & Shale	885 15				
Shale & Shells	1070 185				
Salt & Shale	1290 220				
Shale & Anhydrite	1463 173				
Shale	1480 17				
Sandy Lime	1640 160				
Sand & Shale	1815 175				
Broken Lime, Sandy	1924 109				
Sandy Lime	1990 66				
Lime & Shale	2044 54				
Broken Lime	2160 116				
Shale & Lime	2511 351				
Broken Lime	2729 218				
Lime	2950 221				
Lime & Shale	3222 272				
Lime	3311 89				
Arbuckle Lime	3318 7				
Broken Lime	3339 5				
Total Depth	3339				

12-6-51 Plugged back to 3318'.

5-29-51 Plugged back to 3098'.

RECEIVED
 DIVISION
 SEP 12 1951
 DIVISION
 Wichita, Kansas