

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barton SEC. 7 TWP. 20 RGE. 11W E/W  
Location as in quarters or footage from lines:  
C.S./2 NE NW


Locate Well  
correctly on above  
Section Platt.

Lease Owner Petroleum Energy, Inc.  
Lease Name Schartz Well No. A-2  
Office Address Suite 710 One Twenty Bldg. Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 9-23-81  
Plugging completed 9-30-81  
Reason for abandonment of well or producing formation \_\_\_\_\_

\_\_\_\_\_ Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3351'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out.
				8-5/8"	293'	none
				4-1/2"	3343'	2824'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

~~Moved in on location, took stretch, plugged off bottom with sand to 3300' and set 4 sacks cement. Shot casing @2814' and pulled 70 joints of pipe. Plugged well with 5 sacks hulls, 25 sacks gel, 8-5/8" plug, 140 sacks 50/50 pos, 2% gel, 3% cc. Plugging completed.~~

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF ~~KANSAS~~ Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October, 1981

My Commission expires:



Jane Hoover  
Notary Public  
STATE CORPORATION COMMISSION

OCT 15 1981

CONSERVATION DIVISION  
Wichita Kansas

OPERATOR: Petroleum Energy, Inc. 710 One Twenty Bldg. Wichita, Ks. 67202  
 CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name: Schartz "A" Well No. #2  
 Sec. 7 T. 20 R. 11W Spot C S/2 NE NW  
 County Barton State Kansas Elevation \_\_\_\_\_

Casing Record:  
 Surface: 8 5/8 @ 293' with 175 Sxs. 3%cc  
 Production: \_\_\_\_\_ @ \_\_\_\_\_ with \_\_\_\_\_ Sxs. 2%gel

Type Well: Oil Total Depth 3351'  
 Drilling Commenced: 6-3-81 Drilling Completed 6-10-81

Formation	From	To	Tops
Cellar	0	7	
Shale, Sand	7	870	
Shale, Lime	870	2912	
Lime	2912	3351	

*Prod Casing 3343'*  
*of 4 1/2 w/100 Sacks*  
*FD*

COMPLETION RECORD

Liner Record: Size \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_  
 Cementing Record: \_\_\_\_\_ Sacks \_\_\_\_\_  
 Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production: \_\_\_\_\_

Electric Log \_\_\_\_\_ Type and Depths Covered \_\_\_\_\_

RECEIVED  
 STATE CORPORATION COMMISSION

SEP - 2 1981

CONSERVATION DIVISION  
 Wichita, Kansas