

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Locate well correctly on above  
Section Plat

Rice County. Sec. 11 Twp. 20S Rge. 10W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW SW NE  
Lease Owner Rex & Morris Drilling Company  
Lease Name Scott Well No. 1  
Office Address Box 334, El Dorado, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Jan. 29 19 54  
Application for plugging filed " 19 "  
Application for plugging approved " 19 "  
Plugging commenced " 19 "  
Plugging completed " 19 "  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, Box 597, McPherson, Kansas  
Producing formation None Depth to top Bottom Total Depth of Well 3378 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION        | CONTENT | FROM | TO  | SIZE  | PUT IN | PULLED OUT |
|------------------|---------|------|-----|-------|--------|------------|
| Surface Hole     | Water   | 0    | 227 | 8 5/8 | 221    | None       |
| See Attached Log |         |      |     |       |        |            |
|                  |         |      |     |       |        |            |
|                  |         |      |     |       |        |            |
|                  |         |      |     |       |        |            |
|                  |         |      |     |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pulled 1600' of Drill Pipe: Circulate 30 minutes: Laid down drill pipe:  
Spotted 15 of cement on 15' rock bridge @ 220': Mud to 20' with 5 sacks of cement cap.

2-17-54


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rex & Morris Drilling Company  
Address Box 334, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
C. E. McClure (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. McClure  
Box 334, El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of February 19 54

My commission expires July 23, 1956  
Unifred E. Cunit Notary Public.



15.159.00386.0000

Elevation - 1774 DF

1777 RB

SCOTT WELL # 1  
 REX & MORRIS DRILLING CO.

|                    |                             |                            |             |
|--------------------|-----------------------------|----------------------------|-------------|
| Total Depth        | - 3378                      | Location                   | - SW SW NE  |
| Contractor         | - Rex & Morris Drilling Co. | Section                    | - 11-20-10W |
| Commenced          | - 1-21-54                   | Rice County, Kansas        |             |
| Completed          | - 1-29-54                   | Casing Record:             |             |
| Initial Production | - D & A                     | 8 5/8" @ 221' w/ 150 sacks |             |

| FORMATION            | DEPTH |      |
|----------------------|-------|------|
| Surface Hole         | 227   |      |
| Red Rock             | 400   |      |
| Shale & Shells       | 950   |      |
| Salt, shale & shells | 1050  |      |
| Shale & Lime         | 1200  |      |
| Lime & Shale         | 1765  |      |
| Lime                 | 1785  |      |
| Shale & Lime         | 1925  |      |
| Shale & Shells       | 2345  |      |
| Shale & Lime         | 2530  |      |
| Lime & Shale         | 2537  |      |
| Sand                 | 2583  |      |
| Lime                 | 2797  |      |
| Lime & Shale         | 2875  |      |
| Shale                | 2984  |      |
| Lime                 | 2988  |      |
| Shale                | 3009  |      |
| Lime                 | 3221  |      |
| Lime & Shale         | 3289  |      |
| Conglomerate         | 3335  |      |
| Sand                 | 3346  |      |
| Lime                 | 3378  | T.D. |

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Co.

By

*Paul W. Hunt*

Title

Geologist

STATE OF KANSAS )

) SS

COUNTY OF BUTLER )

Subscribed and sworn to before me, a Notary Public, this 15th day of February 1954.

*Wm. E. O'Neil*  
 Notary Public

My Commission expires:

July 23, 1956

**PLUGGING**  
 FILE SEC 11-20-10W  
 BOOK PAGE 12 LINE 33