

ATE OF KANSAS
ATE CORPORATION COMMISSION
3 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

15-159-19006-00-01
API NUMBER Comp. 12-20-62

RECEIVED

DEC 07 2001

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Kitsy-Minor
WELL NUMBER 3

4950 Ft. from S Section Line
2310 Ft. from E Section Line

SEC. 11 TWP. 20 RGE. 10W (E) or (W)
COUNTY Rice

Date Well Completed _____

Plugging Commenced 11-19-01

Plugging Completed 11-20-01

LEASE OPERATOR B & B Oil

ADDRESS P.O. Box 447, Chase, Kansas 67524

PHONE (620) 938-2588 OPERATORS LICENSE NO. 31940

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Virgil Clothier (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3342'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	205'	None
				4-1/2"	3340'	150'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material used, state the character of same and depth placed, from _____ feet to _____ feet each side. Plugged off bottom with sand to 3100' and 4 sks. cement. Shot pipe @1700', parted 150' down. Ran tubing to 1300' and perforated, pumped 35 sks. cement, pulled up to 900' and perforated, pumped 35 sks. cement, pulled to 250' and perforated, circulated 145 sks. cement to surface. Used 60/40 pos. 4% gel. Layed rest of tubing down.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: B & B Oil

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)


of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 6th day of December 2001

My Commission Expires:



Notary Public