



C O P Y

HILDEBRAND #1

SW/4 NE/4 NE/4 Section 11-20S-10W

Rice County, Kansas

J. C. DOZIER, ET AL

Commenced: May 6, 1948  
Completed: May 17, 1948

Surface Clay and Sand	0	130
Surface Clay	130	221
Shale & Red Bed	221	820
Red Bed	820	860
Shale	860	960
Salt	960	1355
Shale	1355	1385
Shale & Lime	1385	1565
Sand and Shale	1565	1746
Lime	1746	1767
Lime & Shale	1767	1945
Shale & Lime	1945	2250
Lime & Shale	2250	2350
Shale & Lime	2350	2660
Lime	2660	2715
Lime & Shale	2715	2895
Shale & Lime	2895	2976
Lime & Shale	2976	3006
Shale & Lime	3006	3128
Lime	3128	3173
Lime & Shale	3173	3213
Shale & Lime	3213	3281
Lime	3281	3311

CASING RECORD

8-5/8" casing set at 221'  
and cemented with 100  
sacks cement.

4-1/2" casing set at 3300'  
and cemented with 75 sacks  
cement.

TOTAL DEPTH 3311

STATE OF COLORADO )  
                          ) ss  
COUNTY OF EL PASO )

I hereby affirm that the above and foregoing is a true and correct copy of the log of J. C. Dozier, et al, Hildebrand #1 well, located in the Southwest Quarter, Northeast Quarter, Northeast Quarter of Section 11, Township 20 South, Range 10 West, Rice County, Kansas.

LOWELL- VOLTZ, INC.

By /s/ Emil E. Bowers  
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, this 24th day of May, 1948.

S E A L

/s/ Milford L. Pritchard  
Notary Public

My commission expires: December 3, 1951

