



9

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission  
 CONSERVATION DIVISION  
 (Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

January 28, 1963

RECEIVED  
STATE CORPORATION COMMISSION

FEB 8 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Elmo Finch of Pipe Pullers, Inc. has this

date requested permission to plug the following described well:

Mr. Finch guarantees payment of the plugging fee.

Operator's full Name: Ben C. W. Hyde, Jr.

Complete Address: 4722 Broadway, Kansas City 12, Missouri

Lease Name: Kitsey Well No. .2

Location: App. C E/2 SE SW Sec. 11 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 3085' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Finch was instructed to plug the well as follows:

Push 4½" plug to 3055'. Sand to 3045' and cement with  
3 sacks. Fill hole with mud to 190'. Set rock bridge  
from 190' to 180' and cement with 20 sacks. Fill hole  
with mud to 40'. Set rock bridge from 40' to 30' and  
cap hole with 10 sacks cement.

Very truly yours,

  
 Conservation Division Agent