

State of Kansas



FORM - CP-2
Rev. 6-26-62

15.159.30036.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
JUL 6 1965
7-6-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

July 2, 1965

Dear Sir:

Mr. Bert Self of Self Caseing Pulling Co. has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Don P. Ingling

Complete Address: 615 First National Bld'g. Wichita, Kansas.

Lease Name: Glaser Well No. #1

Location: SW-NE-NW Sec. 11 Twp. 20 Rge. 10 (E) (W) #

County Rice Total Depth 3351' Oil Well #

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

2441 ft. of long stringsanded to 2300' & 5 sacks cement. 212' of 8 5/8" surface pipe circulated with cement. Hole filled with mud to 200ft. 10' rock bridge & 20 sacks cement. Hole filled to 40 ft. , 10' rock bridge & 10 sacks cement to base of cellar.

Very truly yours,
Norman Gustafson