



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

November 3, 1962

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

NOV 13 1962 11-13-62
 CONSERVATION DIVISION
 WICHITA, KANSAS

Dear Sir:

Mr. Ray James of Ben C. W. Hyde, Jr. has this

date requested permission to plug the following described well:

Mr. James guarantees payment of the plugging fee.

Operator's full Name: Ben C. W. Hyde, Jr.

Complete Address: 4722 Broadway, Kansas City 12, Mo.

Lease Name: Macemore Well No. 3

Location: SE NE SE Sec. 11 Twp. 20 Rge. 10 (E) (W)

County Rice Total Depth 3114' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. James was instructed to plug the well as follows:

Fill hole with sand to 3050' and cement with 4 sacks.


Fill hol with mud to 195'. Set rock bridge from 195' to

185' and cement with 25 sacks. Fill hole with mud to

30'. Set rock bridge from 30' to 20' and cap hole with

10 sacks cement.

Very truly yours,


 Conservation Division Agent