

State of Kansas



15.159.04455.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202
RECEIVED
NOV 18 1966
11-18-66
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

November 20, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sam Bradley of Pipe Pullers, Inc. has this date requested permission to plug the following described well:

Mr. Sam Bradley guarantees payment of the plugging fee.

Operator's full Name: Ben C. W. Hyde, Jr.

Complete Address: 4722 Broadway, Kansas City 12, Missouri

Lease Name: Miller Well No. 4

Location: C W/2 E/2 Sec. 13 Twp. 20 Rge. 10 (E)(W) X

County Rice Total Depth 3340' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bradley was instructed to plug the well as follows:

Fill hole with sand to 3325' and cement with 5 sacks.

Fill hole with mud to 155'. Set rock bridge from 155' to 145' and

cement hole with 25 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent