

State of Kansas



15-159-02746-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 6 1967  
3-6-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Ow3n Bailey of Santa Fe Pipe & Supply, Inc. has this date requested permission to plug the following described well:

Mr. Railey guarantees payment of the plugging fee.

Operator's full Name: Santa Fe Pipe & Supply, Inc.

Complete Address: Box 562, Great Bend, Kansas

Lease Name: Fatinger Well No. 1

Location: SW SW SW Sec. 13 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 3378 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Railey was instructed to plug the well as follows:

(Tubing shot off in hole at 3133') Fill hole with sand to 3100' and  
cement with 5 sacks. Fill hole with mud to 180'. Set rock bridge  
from 180' to 170' and cement hole with 20 sacks. Fill hole with mud  
to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks  
cement.

Very truly yours,

  
Conservation Division Agent