

15.159.02778.0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1968
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Specter Pipe & Supply Inc.Complete Address: Box 169 Russell, Kansas 67665Lease Name Gill Well No. # 2Location 11W NE NE Sec. 22 Twp. 20 Rge. 10 (E) / (W)County Rice Total Depth 3401'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Lynch Casing Pulling Co.Address: Great Bend, Kansas License No. 457Operation Completed: Hour 10AM Day 21 Month 8 Year 68

The Above well was plugged as follows:

8 5/8"-177'-Circulated w/cement. 5 1/2"-3390'-Cemented. Top Perf. 3060'.

Sand hole to 3000'. 5 Sax.cement 3000' to 2950'. Mud 2950' to 500'.

25 Sax.cement 500' to 400'. Mud 400' to 200'. 25 Sax.cement 200' to 125'.

Mud 125' to 50'. Bridge 50' to 40'. 10 Sax.cement 40' to 0.

Pulled 2625'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging SupervisorDATE 8/23/68
INV. NO. 8330-u