

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION CEL NE-SW

SEC. 7 TWP. 20 RGE. 11 W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 4 Lease Schartz "B"

Operator Morris Mizel & Larry Miller Address Kennedy Bldg. Tulsa, Okla.

Field _____ County Barton

Total Depth 3321 Feet.

Plugging Contractor Bert Self

Plugging Contractor's License No. 48

Address Hutchinson, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" @ 310' C.W.C. 5 1/2" Oil string set
3309' w/ 50 sq cem. Sanded hole to 3300'
dumped 5 sq cem. shot off and pulled 5 1/2"
Casing. Pumped 20 sq fresh fill mud, Plug
and 100 sq cem. Filling surface pipe
from 300' to base of cellar with cem.
Pumping by Halliburton Cem. Co.

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1955

7-22-55 Warren H. Harner
District Conservation Agent

Date July 20, 1955

PLUGGING
FILE SEC 7 TWP 20 R 11 W
BOOK PAGE 136 LINE 34

CONSERVATION DIVISION
Wichita, Kansas