

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-009-22,419

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Thomason Oil Company

Complete Address 2700 Oak Street, Suite A, Hays, Kansas 67601

Lease Name Koch Well No. 1

Location C w/2 SW Sec. 7 Twp. 20 Rge. 11 (~~East~~) (West)

County Barton Total Depth 3350'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations and Filled Cementing Co., Inc.

Address Box 506, Russell, Kansas License No. \_\_\_\_\_

Operation Completed: Hour: 10:45 AM Day: 14 Month: August Year: 1981

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows: 8 3/8" - 253' - 175 sacks Fluv. 1783 & L. Anhydrite 588' - 599'

Circulate hole and fill with mud. Pumped 50 sacks cement through drill pipe at 540'. Pumped 30 sacks cement through drill pipe at 250'. Hole filled with mud to 40'. Plug and 1/2 sack hells pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rthole cemented with 10 sacks cement. Cement used: 50-50 permix w/4% gel and 3% c.c.

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated

INVOICED AUG 18 1981

Signed: [Signature]  
Conservation Division Agent

DATE 9-29-81 CONSERVATION DIVISION  
Wichita, Kansas

NO. 7720-W