

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-009-14373.0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Phillips Petroleum Co.

Complete Address P.O. Box 287, Great Bend, Ks. 67530

Lease Name Pety Well No. 2

Location C-E/2 SW NE Sec. 7 Twp. 20 Rge. 11 (East) (West)

County Barton Total Depth 3332'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No. _____

Operation Completed: Hour: 3:30 PM Day: 11 Month: 8 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 233' S.P. cnc. w/117 sacks common, 5 1/2" set at 3315' w/200 sacks common cement.
Top perf at 3315'. Plugged bottom w/ sand & 5 sacks cement to 2400'. Lost pipe 1 time
& recovered 339'. Ordered 130 sacks 50/50 permix 4% Gel: 3% Cal. Cl., 15 sacks Gel, 5 sacks
hulls & 8 5/8" plug. Pumped into S.P., 4 sacks hulls, 12 sacks Gel, 70 sacks cement, 3 sacks
Gel, 1 sack hulls, released plug & followed w/ 60 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 1000 pounds.

AUG 23 1982

Amount of Surface Casing: 233' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Gilbert G. Schubert
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1982

Signed: _____
Conservation Division Agent

INVOICED

DATE 8-30-82

INV. NO. 9594