

70:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-30023-00-00

Spot: CSW

Sec/Twnshp/Rge: 13-30S-17W

1320 feet from S Section Line, 1320 feet from W Section Line

Lease/Unit Name: RUNNYMEDE

Well Number: 1

County: KIOWA

Total Vertical Depth: 4861 feet

Operator License No.: 5447

Conductor Pipe: Size

feet:

\$157.98

Op Name: OXY USA, INC.

Surface Casing: Size 8.625

feet: 299

WITH 175 SX CMT

Address: PO BOX 27570 5 E GREENWAY PLZ STE
HOUSTON, TX 77227

Production: Size 4.5

feet: 4849

WITH 125 SX CMT

Liner: Size

feet:

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 08/29/2002 2:00 PM

Plug Co. License No.: 5105

Plug Co. Name: CLARKE CORPORATION

Proposal Revd. from: ALAN VRATIL

Company: CLARKE CORPORATION

Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4700' WITH 2 SX CMT. 1ST PLUG AT 1055' WITH 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/29/2002 3:00 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4817'. PERFS AT 4723-4773 (4 SETS). SET CIBP @ 4635' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN CASING & RUN 2 3/8" TUBING IN TO PLUG THROUGH. 1ST PLUG AT 1040' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 315' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 15 SX CMT.

RECEIVED
SEP 16 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2300' OF 4 1/2" CASING.

Plugged through: TBG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

SEP 03 2002

DATE 9-17-02

INV. NO. 2003060515

MP

SEP 2/3