

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- - 097-20,339-0000

SW/4 SEC. 20, T30S, R17W/2

1390 FEET FROM N/S SECTION LINE

1390 FEET FROM W/2 SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # _____

LEASE NAME Both "B" WELL # 1

OPERATOR: TXO Production Corp.

COUNTY Kiowa

NAME & ADDRESS 200 W. Douglas, Suite 300
Wichita Kansas 67202

WELL TOTAL DEPTH 4982 \$161.92 FEET

CONDUCTOR PIPE: SIZE _____ FEET

SURFACE CASING: SIZE 8 5/8" FEET 913

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Clark Corporation LICENSE NUMBER _____

ADDRESS 107 W. Fowler, Medicine Lodge Kans.

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 9 MONTH: 8 YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM Elmo Morgenstern

(COMPANY NAME) Clark Corp. (PHONE) _____

WERE: 1st plug sanded bottom back to 4740' & dumped

2 sky cement on top of sand through bailer. 2nd plug squeezed
through 8 5/8" w/ 2 sky hulls 15 sky gell + 50 sky cement + 10 sky
gell + 1 sky hull + released rubber plug + 100 sky cement. The cementing
was accomplished by Sun's Cementing

PLUGGING PROPOSAL RECEIVED BY Paul A. Luthis
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 9 MONTH: 8 YEAR: 1983

ACTUAL PLUGGING REPORT This hole was plugged as proposed.

Max pressure 500# & shut in @ 500# pressure

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1983 8-15-83

CONSERVATION DIVISION
Wichita, Kansas

REMARKS: They had 496.3' of 4 1/2" production pipe set. They had
perforations @ 4790' to 97'. They recovered 32.50' of 4 1/2"
production pipe.

I (DID / DID NOT) OBSERVE THIS PLUGGING.

SIGNED Paul A. Luthis ✓
(TECHNICIAN)

INVOICED

DATE 8-18-83

INV. NO. 5235-W

FORM CP-2/3
REV. 6-83