

1 051756

12-8

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
220 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-20,444 - 0000  
C E/2 NW, SEC. 22, T 30 S, R 17 W/EX  
3960 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817

Lease Name Iron Mountain Well # 1-22

Operator: Benson Mineral Group

County Kiowa

Name & Address 1560 Broadway, Ste. 1900

Well Total Depth 4952 160.94 feet

Denver, CO 80202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 548

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Benson Mineral Group License Number 5817

Address 1560 Broadway, Ste. 1900, Denver, CO 80202

Company to plug at: Hour: 9 a.m. Day: 8 Month: 12 Year: 19 93

Plugging proposal received from Phillip Kempton

(company name) Benson Mineral Group (phone) 303-863-3500

vars: 5 1/2" at 4950' w/100 sx cement, Perfs at 4834-44'

1st plug set CIBP at 4400' with 2 sx cement on top,

Pump plugs through tubing:

2nd plug at 1000' with 8 sx gel and 50 sx cement,

3rd plug at 600'.with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 8 Month: 12 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4400' and dumped 2 sx cement on top,

Pumped plugs through tubing:

2nd plug at 1000' with 8 sx gel and 50 sx cement,

3rd plug at 600' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Benson Mineral Group. Recovered 2000' of 5 1/2" **RECEIVED**  
(If additional description is necessary, use BACK of this form.) STATE CORPORATION COMMISSION

observe this plugging.

**INVOICED**

DATE DEC 13 1993

Signed *Richard M. Lacey* (TECHNICIAN) DIVISION  
Wichita, Kansas

DEC 10 1993

INV. NO. 29503