

MAY 27 1987

To: 1 070350
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,238 - 0000

SW NE NE, SEC. 5, T 30 S, R 17 W/R

4290 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Barstow "A" Well # 1

Operator: TXO Production Corporation

County Kiowa 117.00

Name &

Address 155 North Market, Suite 1000

Well Total Depth 3600 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 27 Month: 5 Year: 19 87

Plugging proposal received from Allen Dick

(company name) TXO Production Corporation (phone) 316-269-7655

Elevation 2100'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2300-2350'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 500' with 40 sx cement,

3rd plug at 30' below base of surface pipe with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:30 a.m. Day: 27 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2350' with 50 sx cement,

2nd plug at 500' with 40 sx cement,

3rd plug at 290' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 4% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

DATE 6-2-87

Signed Dan Goodrow
(TECHNICIAN)

WELL NO. 17090

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date May 21, 1987 month day year

API Number 15-097-21,238-0000

OPERATOR: License # 5171 Name TXO Production Corp Address 155 N. Market, Suite 1000 City/State/Zip Wichita, Kansas 67202 Contact Person Cory West Phone (316) 269-7655

SW NE NE Sec. 5 Twp. 30 S, Rg. 17 East 4290' Ft. from South Line of Section 990' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5107 Name H-30 Drilling, Inc. City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 990' feet County Kiowa Lease Name BARSTOW Well # 1 Ground surface elevation feet MSL Domestic well within 330 feet yes X no Municipal well within one mile yes X no Depth to bottom of fresh water 100' Depth to bottom of usable water 200' Surface pipe by Alternate 1 X ? Surface pipe planned to be set 250' Conductor pipe required no Projected Total Depth 3600' feet Formation Emporia

Well Drilled For: Oil SWD Infield X Mud Rotary X Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 5-20-87 Signature of Operator or Agent Cory West Title Drlg. & Prod Engineer

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. This Authorization Expires 11-20-87 Approved By 5-20-87

Spud 5-22-87 250' of 8 5/8" R NO WW w/le D.G. called in Allen Dick (TXO) SW NE NE Sec. 5 Twp. 30 S, Rg. 17 East

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1600' Any Base feet depth with 40-50 sxs of Ecenolite 2nd plug @ 900' 500' feet depth with 25-40 sxs of 3rd plug @ 40' 30' Below SP feet depth with 40-40 + bridge sxs of 4th plug @ 40' feet depth with 1.0 sxs of 5th plug @ feet depth with sxs of (2) Rathole with 1/2 sxs (b) Mousehole with 1/2 sxs

Allen Dick TXO

PUSHER Rick Davis TD 3600 FORMATION Emporia SURFACE PIPE 8 5/8 @ 260 ANHYDRITE 2350 ELEVATION 2100 5-27-87 STARTING TIME & DATE 1:00 AM COMPLETION TIME & DATE 5-27-87 4:30 AM 1st PLUG @ 2350 FT. W/ 50 SX 2nd PLUG @ 500 FT. W/ 40 SX 3rd PLUG @ 290 FT. W/ 40 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 10 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Hall w/ 60/40/40 TECHNICIAN Dan

RECEIVED STATE CORPORATION COMMISSION MAY 29 1987 CONSERVATION DIVISION Wichita, Kansas