

1020145

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-21,031 - 0000

E/2 SW SE, SEC. 30, T 30 S, R 17 W/E

660 feet from W/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5152

Lease Name Booth Well # 1-30

Operator: Lee Banks

County Kiowa

Name & Address 200 West Douglas, # 550

Well Total Depth 5100 165 75 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 575

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D. R. Lauck Oil Company License Number 5427

Address 221 South Broadway, Suite 400, Wichita, KS 67202

Company to plug at: Hour: 3:00 pm Day: 7 Month: May Year: 1984

Plugging proposal received from Doyle Folkerts

(company name) D. R. Lauck (phone) 316-793-7713

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 620' with 50 sx cement

2nd plug at 200' with 20 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:40 pm Day: 7 Month: May Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 620' with 50 sx cement, 2nd plug at 200' with 20

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rathole with 15 sx cement, 6th plug to circulate

mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 11 1984  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Buie

(If additional description is necessary, use BACK of this form)

(If needed) observe this plugging.

Signed [Signature] (TECHNICIAN)

INVOICED

DATE 5-14-84

INV. NO. 1492

5-7

MAY 23 1984