

1 030688

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,213 -0000

NW NE NE, SEC. 33, T 30 S, R 17 (W) X  
4920 feet from S section line

890 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8565

Lease Name Wedel Well # 2

Operator: Huey Grey  
Name & Address Rt. 1, Box 47  
Greensburg, KS 67054

County Kiowa 173.06  
Well Total Depth 5325 Simpson feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address P. O. Box 8609, Wichita, KS 67208

Company to plug at: Hour: 4:00 pm Day: 7 Month: April Year: 19 86

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling (phone) 316-682-5513

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite N/A  
Elevation 2148'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 50 sx cement

3rd plug from 40' to surface with 10 sx cement

4th plug to circulate rat hole with 10 sx cement

5th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:30 pm Day: 7 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1085' with 50 sx cement, 2nd plug at 355' with 50 sx cement, 3rd plug from 40' to surface with 10 sx cement, 4th plug to circulate rat hole with 10 sx cement, 5th plug to circulate mouse hole with 10 sx cement.

STATE CORPORATION COMMISSION  
APR 28 1986  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE APR 29 1986

Signed Steve Luthi (TECHNICIAN)

INV. NO. 13579