

To: 1 040450
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-9
API NUMBER 15- 097-21,264-0000
NW NE SW, SEC. 34, T 30 S, R 17 W/E
2300 feet from S section line
3580 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30160
Operator: Clute Oil Corporation
Name & Address 444 17th Street, Suite 608
Denver, CO 80202

Lease Name Booth Well # 1
County Kiowa 169.00
Well Total Depth 5200 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 465

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 11:30 a.m. Day: 9 Month: 8 Year: 19 90

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 5152', PBTD 5112', Perfs at 4998-5012, 5016-28'

1st plug pump 1 sx hulls and 20 sx common cement,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 9 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4800' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 50 psi. 8-14-90

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3710' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE: AUG 23 1990
INV. NO. 29006

Signed Stephen J. Pifer
(TECHNICIAN)