

1 040449

8-9

API NUMBER 15-097-21,276-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 140!
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

E NE NE, SEC. 34, T 30 S, R 17 W/E
4620 feet from S section line
800 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30160

Lease Name Cromer Well # 1

Operator: Clute Oil Corporation
Name & Address: 444 17th St., Suite 608
Denver, CO 80110

County Kiowa 163.80
Well Total Depth 5040 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 463

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:45 a.m. Day: 9 Month: 8 Year: 19 90

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 5038' PBD 5038' Perfs at 5000-5006, 5014-5020'

1st plug sand back to 4940' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 9 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4860' and dumped 4 sx cement on top of sand bridge through bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2578' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

AUG 23 1990

DATE: _____

INV. NO. 29007

Signed Stephen J. Fisher
(TECHNICIAN)