

1041346

21021-0000

TO: STATE CORPORATION COMMISSION

4-28

API NUMBER 15-097-1021
NW NW SW SEC. 1, T 30 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 2190 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 600 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME NICHOLS WELL # D-1

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA

OPERATOR LICENSE # 5506

WELL TOTAL DEPTH 5050 164.13 FEET

OPERATOR: WOOLSEY PETROLEUM CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 3712' WITH 135 SX

NAME AND PO BOX 168 SURFACE CASING: SIZE 8 5/8" @ 485' WITH 125 SX

ADDRESS MEDICINE LODGE, KS 67104

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 28 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 3502-3512, CIBP @ 3490, PERFS AT 3412-3420

SANDED BACK TO 3320' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER.

PUMPED DOWN 8 5/8" WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8"

WIPER PLUG, & 150 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:45 PM DAY: 28 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

SANDED BACK TO 3320' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER.

PUMPED DOWN 8 5/8" WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8"

WIPER PLUG, & 150 SX CEMENT. MAXIMUM PSI @ 500#. SHUT IN WITH 200#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2700' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

STATE OF KANSAS 5-6-99

DATE 5-7-99

MAY 06 1999 SIGNED

REV. NO. 60932

CONSERVATION DIVISION
Wichita Kansas

(TECHNICIAN)

FORM CP 2/3