

1 051003

2-4-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,073 - 0000

C SE NW, SEC. 1, T 30 S, R 18 W/E

3300 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Nichols "F" Well # 1

Operator: TXO Production Corporation
Name &

County Kiowa 164.13

Address 155 North Market, Suite 1000
Wichita, KS 67202

Well Total Depth 5050 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 475

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 4 Month: 2 Year: 19 88

Plugging proposal received from Jerry Collins

(company name) TXO Production Corporation (phone) 316-886-5605

were: 4 1/2" at 5046' PBD 5002' Perfs at 4790-94, 4944-50' Elevation 2151' GL

1st plug pump 1 sx hulls and 25 sx cement to bottom,
2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:50 p. Day: 4 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement to 5000',

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

2-9-88 FEB 09 1988

Maximum pressure 600 psi and shut in 350 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2365' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

(If you observe this plugging.)

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED

DATE 2-10-88

INV. NO. 19817