

4-14-88

97 R

To: 1 061098
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,219 - 0000

SW NE SW, SEC. 3, T 30 S, R 18 W/EX
1950 feet from S section line
3505 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5171

Lease Name Parkin "H" Well # 1
County Kiowa 118.63

Operator: TXO Production Corporation
Name & Address: 155 North Market, Suite 1000
Wichita, KS 67202

Well Total Depth 3650 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 5:30 p.m. Day: 14 Month: 4 Year: 19 88

Plugging proposal received from Elmo Morgenstern
(company name) Clarke Corporation (phone) 316-886-5665
were: 4 1/2" at 3648' PBSD 3634' Perfs at 3482-86, 3489-96'

1st plug sand back to 3430' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 10 sx gel, 50 sx cement, 10 sx gel, 100 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:45 p.m. Day: 14 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3430' and dumped 4 sx cement on top of
sand through bailer,
2nd plug pumped 10 sx gel, 50 sx cement, 10 sx gel, 100 sx cement.

Maximum pressure 450 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2600' of 4 1/2" casing.
(If additional data is necessary, use BACK of this form.)

INVOICED

DATE 4-26-88

APR 19 1988

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 20475
4-14

AUG 3 1988

CONSERVATION DIVISION SEP 12 1988
Wichita, Kansas

FORM CP-2/3
Rev. 01-84